

Isotec and Isotec Luxe Loft Ladder

Ready to install element

Airtightness (a value): class 4 - certified to EN 12114 and EN 1026 by TU Graz

Thermal properties: U-Value lower cover = 0.33 W/m²K (or 0.21 W/m²K with optional secondary upper hatch). Calculated by TU Graz No. B12.137.001.484

Fire Rating: EI₂30 tested according to ÖNORM 3860, EN 1634-1, EN 1363-1. Isotec also available with EI₂60, EI₂90 and EI₂120, which feature an upper cover.

Electric operation:

Available for Isotec, standard sizes only

Stairs:

Steel ladder: 3-part or 4-part folding

Load bearing capacity: 250kg

Tread dimensions: 360mm x 120mm

Custom sizes:

Custom sizes are available on request

Aperture length: 1000mm - 1600mm (Isotec Luxe 1400mm max.)

Aperture width: 500mm - 900mm (Isotec Luxe 700mm max.)


Floor to ceiling height: Up to max. 3400mm

Fire protection certified for a maximum aperture of 1500mm long x 800mm wide.

Space required in mm

Aperture size (length x width)	Floor to ceiling height "A"	Hatch box height	Setdown point approx.* "B"	Swivel range "C"
1100 x 700	2500 - 2600	420mm	1090 (2600)	1390 - 1480
1200 x 600	2500 - 2650	420mm	1085 (2585)	1490 - 1640
1200 x 700	2500 - 2650	420mm	1085 (2585)	1490 - 1640
1300 x 700	2550 - 2750	420mm	1130 (2715)	1620 - 1780
1400 x 700	2550 - 2750	420mm	1130 (2715)	1620 - 1780

*Setdown point varies, depending on floor to ceiling height. Floor to ceiling height shown in brackets



PREMIER LOFT LADDERS
2 Dawson Drive,
Trimley St Mary,
Felixstowe, Suffolk. IP11 0YW
Tel: 0345 9000 195
Fax: 01394 214413
www.premierloftladders.co.uk

© All rights reserved Report all discrepancies Do not scale drawings

Issue	Date	Name	Scale
FIRST ISSUE	14.06.2018	JP	1:10
A	03.10.2019	JP	AT A1

Other sizes and different ceiling heights are available on request
7000301
Isotec & Isotec Luxe
The data on the drawings is for information only. All dimensions must be checked on site. No responsibility is taken for errors.