


Lower hatch door



Eurostep Fire Rated Loft Ladder

Ready to install element

Airtightness (a value): class 4 - certified to DIN EN 12114 by the IFT Rosenheim

Thermal properties: U-Value lower cover = 0.70 W/m²K. Calculated by TU Graz No. B12.137.001.484

Fire Rating: EI₂30 tested according to ÖNORM 3860, EN 1634-1, EN 1363-1.

Electric operation: Standard sizes only

Stairs:

Steel ladder: 3-part or 4-part folding

Load bearing capacity: 250kg

Tread depth: 120mm

Tread width: 250mm or 360mm, subject to aperture width

Custom sizes:

Custom sizes are available on request

Aperture length: 1000mm - 1600mm, subject to ceiling height

Aperture width: 500mm - 1000mm

Floor to ceiling height: Up to max. 3400mm

Fire protection certified for a maximum aperture of 1500mm long x 800mm wide.

Space required in mm			
Aperture size (length x width)	Floor to ceiling height "A"	Setdown point approx. * "B"	Swivel range "C"
1100 x 700	2550 - 2650	1050 - 1310	1480
1200 x 600	2500 - 2650	970 - 1370	1650
1200 x 700	2500 - 2650	970 - 1370	1650
1300 x 700	2550 - 2750	1130 - 1590	1780
1400 x 700	2550 - 2750	1130 - 1590	1780
*Setdown point varies, depending on floor to ceiling height			



PREMIER LOFT LADDERS
2 Dawson Drive,
Trimley St Mary,
Felixstowe, Suffolk. IP11 0YW
Tel: 0345 9000 195
Fax: 01394 214413
www.premierloftladders.co.uk

© All rights reserved		Report all discrepancies		Do not scale drawings	
Other sizes and different ceiling heights are available on request		Date	Name	Eurostep	Scale
	FIRST ISSUE	21.07.2024	JP		1:10
					AT A1
	7000305		The data on the drawings is for information only. All dimensions must be checked on site. No responsibility is taken for errors.		